## Table 6-2 Analysis of Alternatives KRY Site

Alternatives	Protectiveness	Compliance with ERCLs	Mitigation of Risk	Effectiveness and Reliability	Implementability and Practicability	Treatment or Resource Recovery Technologies	Present Cost at 3% Over 100 Years
1 - No Action	No	No	No	No	Yes	No	\$ -
I - NO Action		140	NO	NO	105	NO	ۍ دو. ا
2 - Multi-Phase Extraction and Disposal	Yes (when combined)	Yes (when combined)	Yes (when combined)	Yes (for LNAPL)	Yes	Yes	\$ 9,910,800
3 - LNAPL Extraction and Disposal	Yes (when combined)	Yes (when combined)	Yes (when combined)	Yes (for INAPL)	Yes	Yes	\$ 12,392,100
<ul> <li>4 - Extraction, Ex-Situ Treatment, and Discharge of Groundwater</li> </ul>	Yes (when combined)	Yes (when combined)	Yes (Groundwater contamination) No (LNAPL, sludge, soil contamination)	Yes (for petroleum and PCP) No (for dioxins/furans and metals)	Yes	Yes	\$ 36,223,000
5 - In-Situ Bioremediation of Groundwater and Soil	Yes (when combined)	Yes (when combined)	Yes (PCP and petroleum) No (LNAPL, sludge, dioxin/furan and metals)	Yes (PCP and petroleum) No (dioxin/furans and metals)	Yes	Yes	\$ 52,272,900
6 - In-Situ Chemical Treatment of Groundwater and Soil	Yes (when combined)	Yes (when combined)	Yes (PCP and petroleum) No (LNAPL, sludge, dioxin/furan, metals)	Yes (PCP and petroleum) No (metals) Maybe (dioxins/furans)	Yes	Yes	\$ 14,211,400
7 - Soil Barriers	Yes (when combined)	Yes (when combined)	Yes (when combined)	Yes (when combined)	Yes	No	\$ 5,599,800
8 - Excavation, Off-Site Disposal	Yes (when combined)	Yes (when combined)	Yes (for soils) No (for LNAPL and groundwater)	Yes (for soils)	Yes	No	\$120,950,900
9 - Excavation, Ex-Situ Treatment, and Backfill	Yes (when combined)	Yes (when combined)	Yes (for soils) No (for LNAPL and groundwater) Maybe (dioxin)	Yes (when combined)	Yes	Yes	\$8,469,985.00